

DEMOLITION WORKS

S/NO.	ACTIVITY.	QTY	UNIT	RATE(Rs)	AMOUNT(Rs)
1	DISMANTLING WORK.				
1.1	Removal / Dismantling of Existing Pathway/Arcade consisting of R.C.C columns, slabs, chajja and mosaic flooring etc, complete in all respect including removal of debris from site and its disposal complete.(only flat area of slab shall be measured for payment).				
	Refer Drawing.	2353	Sft.		
1.2	Removal / Dismantling of Existing masonry walls, floor & wall chipping, partition, glass partitions, doors, windows, false ceiling, electrical fixture, wiring etc. present at site complete in all respect without any damages for existing structure/finishes to be retained including removal of debris from site and safely handling over the reusable items identified by IBA. (only flat area of slab shall be measured for payment).				
	Refer Drawing.	11390	Sft.		
TOTAL ESTIMATED COST OF DEMOLITION WORK. Rs					